LS/PARTITION KEY

BRITISH GYPSUM GYPWALL CLASSIC PARTITION SYSTEM: CONSISTING OF ONE OUTER LAYER OF 15mm DURALINE BOARD & ONE INNER LAYER OF 15mm SOUNDBLOC BOARD EACH SIDE OF 70mm GYFRAME 'C' STUDS AT 400mm CENTRES. 50mm ISOWER APR 1200 IN THE CAVITY. (OVERALL THICKNESS OF PARTITION 132mm). 90MIN FIRE RATING.

BRITISH GYPSUM GYPWALL EXTREME PARTITION SYSTEM: CONSISTING OF ONE OUTER LAYER OF 15mm RIGIDUR H BOARD & ONE INNER LAYER OF 15mm SOUNDBLOC BOARD EACH SIDE OF 70mm ACOUSTUDS AT 400mm CENTRES ON THE 1ST FLOOR AND 400mM CENTRES ON THE 2ND FLOOR. 50mm ISOWER APR 1200 IN THE CAVITY. (OVERALL THICKNESS OF PARTITION 132mm). 90MIN FIRE RATING.

BRITISH GYPSUM SHAFTWALL PARTITION SYSTEM. CONSISTING OF 92mm METAL 'I' STUDS WITH GYPROC CORERBOARD BETWEEN STUDS, 25MM ISOWER APR 1200 CAVITY INSULATION AND WITH ONE OUTER LAYER OF 15mm RIGIDUR H BOARD AND ONE INNER LAYER OF 12.5mm FIRELINE BOARD TO NON-SHAFT SIDE. (OVERALL THICKNESS OF PARTITION 122mm). 90 MIN FIRE RATING.

EXISTING MASONRY WALLS - VARIOUS THICKNESSES.

BLOCKWORK WALL - SEE NBS F10

BRICKWORK WALL - SEE NBS F10

C1 PLASTERBOARD BOXING OUT: CONSISTING OF TREATED TIMBER FRAMING WITH 1 OUTER LAYER OF 15MM THICK DURALINE BOARD, 1 INNER LAYER OF 12.5MM THICK WALLBOARD AND 25MM ISOWER APR 1200 INSULATION.

C2 PLASTERBOARD BOXING OUT: CONSISTING OF TREATED TIMBER FRAMING WITH 1 OUTER LAYER OF 15MM THICK RIGIDUR H BOARD, 1 INNER LAYER OF 12.5MM THICK WALLBOARD AND 25MM ISOWER APR 1200 INSULATION.

*NOTE: DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECT'S FINISHES SCHEDULE

FINISHES KEY:

FLOOR FINISHES:

F1 INTERNAL CERAMIC TILING: ANTI-SLIP CERAMIC TILING. SEE NBS SPEC. SECTION M40. COLOURS AS PER FINISHES SCHEDULE DRAWINGS C800 SERIES.

F2 VINYL: TARKETT VINYL FLOORING. SEE NBS SPEC. SECTION M50. COLOURS/TYPE AS PER FINISHES SCHEDULE DRAWINGS C800 SERIES.

F4 EXTERNAL WALKWAY TERRACES CERAMIC TILING: EXTERNAL QUALITY ANTI-SLIP CERAMIC TILING. SEE NBS SPEC. SECTION M40. COLOURS AS PER FINISHES SCHEDULE DRAWINGS C800 SERIES.

F5 RAISED COMPUTER FLOOR WITH ANTI-STATIC TILES - REFER TO M&E DRAWINGS AND SPECIFICATIONS.

F6 ENTRANCE CLEAN-OFF MATTING: SEE NBS SPEC. SECTION H10. REFER TO FINISHES SCHEDULE DRAWINGS C800 SERIES.

WALL FINISHES:

W1 DULUX TRADE STERISHIELD QUICKDRYING EGGSHELL ANTI-BACTERIAL PAINT. SEE NBS SPEC. SECTION M60. COLOURS AS PER FINISHES SCHEDULE DRAWINGS C800 SERIES.

W2 CERAMIC TILING (TOILET & SHOWER WALLS): SEE NBS SPEC. SECTION M40. COLOURS AS PER FINISHES SCHEDULE DRAWINGS C800 SERIES.

W3 CERAMIC TILED WORKTOP SPLASHBACK (KITCHENS AND UTILITY SLURICE AREAS): SEE NBS SPEC. SECTION M40. COLOURS AS PER FINISHES SCHEDULE DRAWINGS C800 SERIES.

CEILING FINISHES:

C1 BRITISH GYPSUM CASOLINE MF SUSPENDED CEILING SYSTEM. CONSISTING OF 1 INNER LAYER 12.5MM THICK SOUNDBLOC BOARD WITH 1 OUTER LAYER OF 15MM THICK RIGIDUR H BOARD (UPPER GROUND, 1ST AND 2ND FLOORS. LOWER GROUND TO HAVE SOUNDBLOC LAYER ONLY). SEE NBS SPEC. SECTION K10.

C3 BRITISH GYPSUM GYPLINER UNIVERSAL SYSTEM: FIXED TO UNDERSIDE OF JOISTS/BATTENS. SEE NBS SPEC. SECTION K10.

C4 FIRE PROOFING TO UNDERSIDE OF TIMBER FLOOR: CONSISTING OF TWO LAYERS OF 12.5MM THICK GYPROC FIRELINE BOARD DIRECTLY FIXED TO UNDERSIDE OF JOISTS. SEE NBS SPEC. SECTION K10.

C5 12MM THICK CEMENT BOARD CEILING ON TREATED SOFTWOOD TIMBER FRAMING. CEMENT BOARD TO RECEIVE AN ACRYLIC RENDER SYSTEM FINISH. TIMBER FRAMING TO BE FIXED TO EXISTING STRUCTURAL BEAMS SLAB. SEE NBS SPEC. SECTION K11, M20 & G30.

C7 HINGED ACCESS METAL CEILING SYSTEM FOR CORRIDOR AREAS. MUST BE SUITABLE FOR MENTAL HEALTH & SECURE FACILITIES (ANTI-LIGATURE).

C8 ARMSTRONG DUNE SUPREME TEGULAR GRID SUSPENDED CEILING SYSTEM. SEE NBS SPEC. SECTION K40.

WALL PROTECTORS & GUARDS:

UPPER GROUND EM WARD CORRIDORS TO RECEIVE ANTI-LIGATURE WALL HANDRAIL

ALL CORRIDOR WALLS TO RECEIVE CORNER GUARDS AT CORNER LOCATIONS:
Acrogrn Surface Mounted Corner Guard SM-10/ SM-20. To be installed in strict accordance with the manufacturers recommendations and instructions.

ROOM EQUIPMENT AND FURNITURE:

PLEASE REFER TO SEPARATE GHA ROOM DATA SHEETS FOR DETAILED EQUIPMENT AND FURNITURE REQUIREMENTS OF EACH ROOM.

NOTES
Do not scale from this drawing. Only figured dimensions are to be taken from this drawing

Contractor must verify all dimensions on site before commencing any work or shop drawings.

Work within the Gibraltar Construction (Design & Management) Regulations is not to start until a Health and Safety Plan has been produced.

This Drawing is Copyright and must not be reproduced without consent of GCArchitects

This drawing originates from the CAD file :
Projects1 ?

Rev.	Description	Drawn	Date	Ch'kd	Date
A	UPDATED TO REFLECT FEBRUARY 2012 CLIENT APPROVED LAYOUTS.	JOR	08.03.12		

DRAINAGE NOTE:

DRAINAGE AS PER M&E ENGINEER'S DETAILS AND SPECIFICATIONS.

FITTINGS NOTES:

- PLEASE REFER TO DOOR SCHEDULE C305 (BLOCK C) & C308 (BLOCK D) & DOOR TYPES DRAWINGS C302 & C303 (BLOCK C) & C306 (BLOCK D) AND ALSO NBS SECTION L20 FOR INFORMATION ON ALL DOORS.

- PLEASE REFER TO WINDOW SCHEDULE C304 (BLOCK C) & C307 (BLOCK D) AND WINDOW TYPES DRAWINGS C300 & C301 (BLOCK C) & C306 (BLOCK D) AND ALSO NBS SECTION L10 FOR INFORMATION ON ALL WINDOWS.

- ALL KITCHENS TO HAVE NEW KITCHEN WORKTOP WITH NEW KITCHEN SINK, BASE UNITS, WALL UNITS, OVEN, COOKER AND EXTRACT HOOD TO SPECIALIST DESIGN. (SEE NBS SPEC. SECTION N11).

- FOR DETAILS OF SANITARYWARE SEE NBS SPEC. SECTION N13.

- FITTINGS & FIXTURES WITHIN PATIENT AREAS TO COMPLY WITH CURRENT ANTI-LIGATURE RECOMMENDATIONS. APPROVAL FROM THE GHA OF ALL ANTI-LIGATURE FITTINGS & FIXTURES WILL BE REQUIRED BEFORE THESE ARE ORDERED BY THE CONTRACTOR.

- DRAWINGS AND